

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Houghton

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>52N</u> R <u>36W</u>	J8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>52N</u> R <u>36W</u>	15
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

J8 May 26 1998  
 J8 May 19 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	24							
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


(J8) Center of Section 23. Corner not established in the original survey. The corner is shown on several surveys recorded in the Houghton Co. record as 1 1/2" iron pipe. See Vol. 1 Pages 631 and 637. 1979 measurement west to 1/4 by Robert A. Mick, RLS is 2607.14'. 1981 measurement west to 1/4 by H. Lawrence O'Donnell, RLS is 2608.19'. Witnesses to corner by R.A. Mick, 1979: N40W 12.2' 9" Maple, S24E 11.1' 12" Y. Birch, N82E 13.1' 18" Maple.  
 (15-Sec. 23) West 1/16 corner between Sections 23-26. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J8) Found a 2" iron pipe at record bearing and distance from the 1979 N40W 9" maple witness by R.A. Mick, in good condition. My measurements show that this pipe is 0.7' North and 5.2' West of the intersection of straight lines between quarter corners. I find the distance west to the quarter corner to be 2606.60'. I accept the pipe as a careful and faithful determination of the position for the corner. At the position of the found pipe and the corner, I place a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.  
 (15-Sec. 23) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Section corner 1343.35' west and Quarter corner 1343.35' east. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a yellow plastic cap which is stamped "MICH DNR PS 33986". Placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J8) Set 1" pipe with 4" MDNR cap.	(15) Set 1" pipe with yellow plastic cap. Blazed and scribed the following:
10" Sugar S02W 5.5' "C1/4 BT"	14" Double Sugar N46E 14.4' "1/16S BT"
7" Sugar N67E 7.55' do	6" Triple Sugar S29E 21.6' do
10" Sugar N09E 15.85' do	8" Sugar S80W 11.6' do
7" Maple N41W 12.8' do	8" Triple Sugar N25W 28.5' do
Bearings are magnetic. Distances are to notch in lower blaze.	Placed a squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4-6-99

For the Michigan Department of Natural Resources - Forest Management Division