

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T52N R 36W	K7
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 19 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7											●		
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K7) Corner common to Sections 13-14-23-24. Established in 1846 by Sylvester Higgins: "North between Section 23 & 24...80.00 Set post cor. Sec 13, 14, 23, 24. Hemlock 20 N20E 34, Maple 8 S35W 11." The original notes also show meander corners set on the section lines 5.00 chains west and 1.00 chains north. The corner is shown on a drawing by C.A. Gibbs, probably ca. 1910-1920, on file at the office of Houghton Co. Equalization, as being monumented by an "I.P." 2617.60' east of an I.P. at J7. This drawing also shows an I.P. on line between J7 and K7, 1889.1' east of J7. The original GLO measurements to adjacent section corners North, East, and South are 80.00 ch (over the lake trigonometrically), 79.89 ch, and 80.00 ch, respectively.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) The original post and accessories were not recovered. Recovered and accepted as the best available evidence of the position of the original corner, a 2" ID iron pipe, projecting 1.2' above the ground, 2614.75' easterly from a 1 1/4" iron pin monumenting J7. The I.P. east of J7 noted above was recovered 1887.81' east of J7 and 1.98' north of a line between J7 of record and K7 described here. The original meander corners were not recovered but the existing shoreline 1.0 ch. north and 4.0 ch. west corroborates the position. I found the distances North, East, and South to section corners as follows: Northerly 85.08 ch to a 1.5" iron pipe in the June 1946 position noted by W.A. Waara, Copper Range Co., Easterly 79.40 ch to a 1/2" pipe noted as the corner in Sept. 1943 by W.A. Waara, and Southerly 80.29 ch. to a corner recorded by Billy D. Buckler, RLS in 1964. I left the pipe at K7 in place and marked new witnesses as described below. Corner recovered and re-witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Found 2" iron pipe.
 Blazed and scribed the following:
 4" twin Maple S10W 4.35' "S23 NBT"
 5" Cedar N45W 19.40' (slope) "S14 NBT"
 9" Sugar N54E 10.65' "S13 NBT"
 7" Sugar S50E 27.9' "S24 NT"
 SE corner of camp bldg. N30W 30'.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4-6-99

For the Michigan Department of Natural Resources - Forest Management Division