

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>34</u> T <u>52N</u> R <u>36W</u>	<u>W-E 1/64 27;34</u>
3. Miscellaneous Property in Sec.	S <u>34</u> T <u>52N</u> R <u>36W</u>	<u>SW-NE 1/64</u>
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SW- Dec 09 1999
 W-E Nov 29 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (W-E 1/64 27;34) The West-East 1/64 corner between Sections 27 and 34. Also known as the NE corner of the NW1/4 of the NW1/4 of the NE1/4 of Section 34. Corner not established in the original survey. Found no subsequent record
 (SW-NE 1/64) Southwest-Northeast 1/64 corner of Section 34. Also known as the Center of the Southwest 1/4 of the Northeast 1/4 of Section 34. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(W-E 1/64 27;34) Established the corner midway and on a line of mean true bearing between Quarter corner 678.05' west and 1/16 corner (unmonumented) 678.05' east, being one-fourth the distance between corners H11 and I11, as monumented and recorded. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, stamped "S27 W-E 1/64 S34 T52N R36W PS33986 11-29-99". From the corner monumented, I found a 3/4" ID iron pipe, placed by Ed Charles RLS, shown on his survey dated 11/10/81, being Drawing number S85-209, 0.23' West and 0.67' North.
 (SW-NE 1/64) Established the corner by regular subdivision of the NE 1/4 of the section, at the intersection of straight lines connecting opposite 1/64 corners (all currently unmonumented). At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, stamped "T52N R36W Center of SW1/4 of NE1/4 Sec 34 PS33986 12-9-99". I also placed a 1" pipe with a yellow plastic cap on the 1/64 line 78.76' south of this corner, 20' north of the water's edge of Emily Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(W-E 1/64) Set 1" pipe w/ 4" MDNR cap.	(SW-NE 1/64). Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:	Blazed and scribed the following:
9" Maple S54W 4.85' "1/64S BT"	7" Maple N42E 30.0' "1/64S BT"
5" Sugar N11W 27.2' do	18" W.Pine S69E 22.5' do
11" Y.Birch N65E 70.0' do	24" W.Pine S31W 53.9' (slope) do
12" Maple S34E 23.2' do	10" Spruce N51W 29.2' do
Placed a squared balsam post adjacent.	Placed squared spruce post adjacent.
Bearings are magnetic. Distances are to notch in lower blaze.	Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/11/00

For the Michigan Department of Natural Resources - Forest Management Division