

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Houghton	Located in:	Corner Code #
(County)		
<b>1. Public Land Survey</b>	T <u>52N</u> R <u>36W</u>	<u>A11</u>
	T <u>52N</u> R <u>36W</u>	<u>A10</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
<b>2. Property Controlling in Section</b>	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
<b>3. Miscellaneous Property in Sec.</b>	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 30 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(A11) Corner common to Sections 25-36 T52N-R37W and 30-31 T52N-R36W. 1845: Established by Wm.A. Burt. Set post corner of Secs. 25 & 36. Sugar 12 S51W 34, Sugar 10 N47W 52.  
 (A10) Quarter corner common to Section 25 T52N-R37W and Section 30 T52N-R36W. 1845: Established by Wm.A. Burt. Set qr. Sect. post. Fir 14 S31W 28, Fir 10 N7W 14. 1945: William Maara reports - Found I.P. on side hill sloping E. to Sleepy Riv. in stand of hwd. & hem. timber. Found old names on 12" Ced. N22W 12 ft. Found old names on 14" Bal. stub 10' high N43E 8 ft. Put names on 7" Bal. N85W 4 ft. 1964: Billy D. Buckler found 1-1/4" iron pipe "re-witnessed as found by Copper Range Company. No original evidence". 11" Hard Maple S52E 42 links, 15" Cedar N17E 44 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(A11) Original post and accessories were not recovered. Found a 1-1/4" ID iron pipe projecting about 1 foot. Distances 2669.2' north and 2625.1' south to found iron pipes compare approximately with the original record. Distance west 5306.4' to found iron pipe matches fairly well with original record 79.9 chains (considering that the subdivision was done by S.W. Higgins). Accepted the pipe as the best available evidence of the position of the original corner.  
 (A10) Found and accepted a 1-1/4" ID iron pipe at record bearing and distance from the 1964 NBTs and from the 1945 Cedar signature tree NW. Made new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(A11) Found 1-1/4" ID iron pipe. Blazed and scribed:	(A10) Found 1-1/4" ID iron pipe. Blazed and scribed:
9" Sugar N58E 26.7'      "S30 NBT"	24" Cedar N69W 26.3'      "1/4S NBT"
14" Y. Birch S57E 10.0'      "S31 NBT"	14" Cedar N15W 11.0'      do
15" Y. Birch South 8.5'      "S36 NBT"	(This cedar is the 1945 signature tree)
4" Sugar N44W 14.1'      "S25 NBT"	The 1964 NBTs:
Set Squared cedar post adjacent.	16" Cedar N21E 29.6' scribing visible
Bearings are magnetic. Distances to notch in lower blaze.	11" Sugar S49E 27.5'      do
	Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 9/25/01  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management