

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>21</u> T <u>52N</u> R <u>36W</u>	<u>1/64 W. of 6</u>
	S <u>21</u> T <u>52N</u> R <u>36W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 19 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(1/64 corner west of #6) The C-W-NE 1/64 corner Section 21, being the NE corner of the West 1/2 of the SW1/4 of the NE1/4, Sec. 21. Not established in the original survey.  
 (7-Sec. 21) North 1/16 corner between Sections 21-22. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1/64 corner west of #6) Established the corner midway and on a straight line between 1/16 corners #5 and #6.  
 (7-Sec. 21) Established the corner midway and on a straight line between 1/4 corner 1325.04' South and Section corner 1325.04' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1/64) Set 1"IDx32" I.Pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 6" Sugar N64E 22.9'      "1/64S BT" 4" Sugar S51E 19.5'      do 5" Sugar S53W 44.5'      do 5" Sugar N59W 26.5'      do Placed a sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 10" Sugar S68E 0.8'      "1/16S BT" 11" Sugar S20E 12.4'      do 9" Sugar S86W 25.6'      do 8" Sugar N54W 9.7'      do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/14/2003