

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>    </u> R <u>    </u>	<u>                    </u>
	T <u>    </u> R <u>    </u>	<u>                    </u>
	T <u>    </u> R <u>    </u>	<u>                    </u>
	S <u>30</u> T <u>52N</u> R <u>36W</u>	<u>C-W-NE 1/64</u>
2. Property Controlling in Section	S <u>30</u> T <u>52N</u> R <u>36W</u>	<u>7</u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>                    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>                    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>                    </u>
4. Lot No. <u>          </u> , Recorded Plat <u>                    </u>		
5. Private Claims		

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Nov. 14, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 (C-W-NE 1/64 - Sec. 30) The Northeast corner of the W1/2 of the SW1/4 of the NE1/4 of Section 30. Not established in the original survey.

(7-Sec. 30) North 1/16 corner between Sections 29 and 30. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (C-W-NE 1/64 - Sec. 30) Established the corner midway and on a straight line between 1/16 corner #5 and 1/16 corner #6, Section 30, 634.11' west and east, respectively.

(7-Sec. 30) Found a 1.5" O.D. iron pipe, in good condition, 0.92' south and 0.10' west of a position which is midway and on the Section line between Section corner 1307.73' north and Quarter corner 1307.73' south. Accepted the pipe as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (1/64) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. (7) Found 1.5" o.d. Iron pipe. Set measuring nail with MDNR tag in the side of:  
 Set measuring nail with MDNR tag in the side of:  
 6" Sugar N23E 10.75' mrkd "1/64S BT" 8" W.Pine S76E 12.0' mrkd "1/16S BT"  
 8" Sugar S87E 24.2' do 6" Maple S33W 33.9' do  
 9" Sugar South 23.4' do 24" W.Pine N80W 11.2' do  
 7" Sugar N65W 29.3' do 7" Hemlock N18W 39.6' do  
 Set sq'd cedar post adjacent. Bearings are magnetic. Set sq'd cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 12/17/07

Surveyor's Michigan License No. 33986