

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 36W	H3
	T 52N R 36W	I4
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on H3 08/17/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H3) Quarter corner common to Sections 3 and 10. 1846 - Established by Hiram and Sylvester Higgins, Deputy Surveyors, midway and on the Section line between Section corners 40.01 chains east and west. Set post. Ironwood 10" N25W 17 links, Sugar 14" S20E 14 links. Found no subsequent record.

(I4) Quarter corner common to Sections 10 and 11. 1846 - Established by Hiram and Sylvester Higgins, Deputy Surveyors, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Sugar 14" N30W 3 links, Sugar 12" S55E 45 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H3) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2692.60' east and west, proportionate to the original record.

(I4) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2610.52' north and south, proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Sugar N33E 2.25' mrkd "1/4S NBT"  
 10" Y.Birch S66E 38.1' do  
 15" Sugar S82W 7.15' do  
 9" Sugar N29W 9.4' do  
 Sq'd cedar post adjacent. Bearings magnetic.

(I4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 11" Sugar N29E 32.1' mrkd "1/4S NBT"  
 15" Sugar S47E 11.9' do  
 5" Sugar S19W 23.0' do  
 12" twin Sugar N77W 26.4' do  
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/30/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16505  
16508