

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>52N</u> R <u>36W</u>	<u>I5</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/19/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(I5) Corner common to Sections 10-11-14-15. 1846 - Established by Hiram and Sylvester Higgins, Deputy Surveyors. Set post. Sugar 6" N70W 8 links, Sugar 6" S40E 14 links. 1963 - Billy D. Buckler RLS found and accepted a 1.5" iron pipe set by unknown party. Several blazed trees in vicinity. Also possible Sugar 6" B.T. N70W 08 links standing. Other B.T. Sugar 6" S40E 14 links (down and rotted). New witnesses: 9" Hemlock S40E 26 links, 12" Hemlock twin S77W 48 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I5) Found a 1.5" ID iron pipe projecting approx. 3' above ground at record bearing and distance from the 1963 witnesses: The Hemlock twin SW is in good condition with overgrown blazes, the Hemlock SE is dead and down. Also at record bearing and distance is the possible BT Sugar NW noted in the 1963 record, in good condition with Vulcan Corp. location poster attached. Accepted the pipe as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I5) Found 1.5" ID Iron pipe.  
 Set measuring nail with MDNR tag in the side of:  
 16" twin Hemlock S78W 32.0' 1963 NBT  
 9" Hemlock N79E 23.8' mrkd "S11 NBT"  
 12" Sugar S56E 15.45' "S14 NBT"  
 20" Sugar N68W 5.4' "S10 NBT"  
 Sq'd cedar post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski Date 08/30/2010  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division