

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S 28 T 52N R 36W	_____	2
	S 28 T 52N R 36W	_____	6
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on 05/19/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 28) East 1/16 corner between Sections 21 and 28. Not established in the original survey.

(6-Sec. 28) Northeast 1/16 corner, Section 28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 28) Established the corner midway and on the Section line between Quarter corner 1341.32' west and Section corner 1341.32' east.

(6-Sec. 28) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
11" Tamarack N20E 25.95' mrkd "1/16S BT"
4" Maple S89E 5.55' do
5" Cedar S06W 18.35' do
6" B.Ash N20W 4.65' do
Set sq'd post adjacent. Bearings are magnetic. | (6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
14" Y.Birch N53E 8.35' mrkd "1/16S BT"
12" double Maple S20W 13.6' do
9" Spruce S59W 13.0' do
13" Spruce N34W 5.3' do
Set sq'd post adjacent. Bearings magnetic. |
|---|--|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/17/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities