

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 52 N.R. 35 & 36W


Houghton COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 30, 31, 25 and 36.

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 9/11/63

WITNESSES TO CORNER..... 12" Soft Maple (S. 31 N.B.T.) S. 28° E., 24 lks.



CIRCLE CORNER REGISTERED

14" Soft Maple (S. 36 N.B.T.) S. 42° W., 54 lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from one Y. Birch B.T. bearing S. 35° E., 29 lks. (a dead stub with scribe marks plain) and a down Hemlock, B.T. bearing N. 30° W., 29 lks. Record indicates this B.T. as "N. 22° W., 19 lks."

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 3/4/65
REGISTERED LAND SURVEYOR