

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 52 N.R. 36 & 35W


Houghton COUNTY

DESCRIPTION OF CORNER Sec. Cor. for T52N R36W, 24, 25, 19 and 30 T52 N R35W.

CORNER MONUMENT 1" Iron pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 9-11-63

WITNESSES TO CORNER..... 12" H. Maple (S. 30) (N.B.T.) S. 67° E., 13 lks.



12" H. Maple (S. 19) (N.B.T.) N. 26° E., 35 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from 1" Iron pipe and B.T. (24" Hemlock, N. 61 W., 35 lks.) down, but scribe marks on upper face plainly visible. Stump badly rotted at Proper distance and bearing (22" Hemlock N. 36° E., 17 lks.)

SURVEYOR'S SEAL

SIGNED Billy D. Buckles DATE 3/5/65
REGISTERED LAND SURVEYOR