

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

(County)

Located In:

Corner Code #

1. Public Land Survey

T 52N R 36W A7

T 52N R 36W B5

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on October 18, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(A7) Corner common to Sections 18-19 T52N-R36W and Sections 13-24 T52N-R37W. Corner established in 1845 by Wm. A. Burt. "80.00 Corner of Sections 13&24 and set post. Sugar 10 S39W 61, do 12 N37W 29". Corner noted in Mead records as 1 1/2" iron pipe found January 24, 1966 with the following witnesses: 7" Elm (C&H tag) 7" Hard Maple (Yellow tag). Found no subsequent record.

(B5) Quarter corner common to Sections 7-18. Corner re-monumented in 1964 by Billy D. Buckler, RLS at location of a wood post placed by Copper Range Company. Corner monumented by a 1" iron pipe with 4" aluminum cap and the following NBTs: 7" H. Maple S25E 36.5 links, 6" Ironwood N47W 24.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A7) Original post and accessories not recovered. Recovered a 1 1/2" iron pipe with 8" Sugar Maple and yellow Vulcan tag facing. The 7" elm with C&H tag noted in 1966 is dead and has recently fallen. Distance north 1/2 mile to probable original 1/4 corner and 1 mile to original section corner check reasonably well with the original record. I accepted the pipe as the best available evidence of the position of the original corner. Left the pipe in place and marked 4 witnesses as described below.

(B5) Found and accepted Buckler's monument, as described, in good condition, and at record bearing and distance from his 1964 NBTs. Left the monument in place and marked three new witnesses as described below. Distance west to original corner is about .5 ch longer than record - an index error found to be common in this area of the township. Also, distance to streams 11.6 ch. and 22.6 ch. east check with the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

(A7) Found 1 1/2" iron pipe. Blazed and scribed the following new bearing trees:

9" Sugar found with Vulcan tag
S18W 7.0' "S24 NBT"
5" Sugar S48E 21.1' "S19 NBT"
10" Sugar N42E 20.9' "S18 NBT"
12" Sugar N18W 26.4' "S13 NBT"

Bearings are magnetic.

(B5) Found 1" iron pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees:
7" Sugar N42E 28.0' "1/4S NBT"
14" Hemlock S65W 46.8' "1/4S NBT"
9" Sugar S04W 12.9' with Copper Range tag. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10-26-95

For the Michigan Department of Natural Resources - Forest Management Division