

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Houghton

(County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 36W	CS
	T 52N R 36W	E6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

E6 October 18, 1995

I, Stephan J. Szyszkoski, in a field survey on CS October 12, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	29	28	27	26	25								
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(CS) Corner common to Sections 7-8-17-18. Established in 1846 by Hiram Higgins: "80.00 Set post cor Sec. 7,8,17,18...Sugar 13 S60N 36, do 15 N75E 38". Line notes north between 17-18: "...58.00 Enter low swale round pond, 62.70 Pond 3.3 over circular, 66.30 over pond, 68.32 Sugar 16 on hill, 80.00 Set post. West Random between 7-18: 17.50 Stream 2 NW in ravine, 22.50 Stream 2 NW in ravine, 28.50 Stream 1 NW in ravine...80.09 West Boundary".

(E6) Quarter corner common to Sections 16-17. Corner established in 1846 by Hiram Higgins: "40.00 Set 1/4 Section post. Sugar 14 S30E 29, Sugar 10 N50W 27." Mead records show "2" iron pipe 2.5' above ground September 12, 1967. 4" Hemlock post at cor. Blue ribbons on Poyhonen log rd. app. 6 chains N. of cor."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(CS) Original post and accessories not recovered. Found no evidence of subsequent monumentation. Remonumented the corner at indexed record distances north of the well defined north edge of the pond noted above (now more a marsh) and east of the streams at 17.50 and 28.50. This position results in 1/2 mile north 0.8 ch. longer than record, mile south 4.95 ch. longer than record, 1/2 mile west .235 ch. longer than record, and 1/2 mile east 2.34 ch. shorter than record. The index correction used was 0.531 ch./40 chains and is the mean of 6-1/2 mile lines measured in this area. I did not use proportionate measurement to reestablish this corner because of the apparent errors in the original survey. The position monumented results in reasonable distances to corners north and west and creates fewer discrepancies with the original record than proportionate measurement would. At the position for the corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

(E6) Original post and accessories not recovered. Found 1 1/2" dia. iron pipe with Copper Range location poster on an 18" sugar facing it. distance north to stream 13.25 chains checks very well with the original record. Distance south to monumented section corner is about 0.39 ch. longer than record - an average common in this part of the township. Accepted the pipe as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(CS) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following new bearing trees:  
18" Sugar N31E 3.1' "S8 NBT"  
8" Basswood S14W 9.1' "S18 NBT"  
7" Sugar S66E 24.3' "S17 NBT"  
8" Sugar S89W 14.0' "S18 NBT"  
Bearings are magnetic. An old blazed line south is about 15' west.

(E6) Found 1 1/2" iron pipe.  
Blazed and scribed the following new bearing trees:  
18" Sugar N39E 9.6' "1/4S NBT"  
16" Sugar S64E 19.7' "1/4S NBT"  
7" Sugar S22W 15.2' "1/4S NBT"  
10" Sugar W48W 26.8' "1/4S NBT"  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10-26-95

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division