

41.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

(County)

Located In:

Corner Code ~~≠~~

1. Public Land Survey	T	<u>52N</u>	R	<u>36W</u>	<u>C6</u>
	T	<u>52N</u>	R	<u>36W</u>	<u>E5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling In Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

E5 October 19, 1995

I, Stephan J. Szyszkoski, in a field survey on C6 October 17, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17-18. Established in 1846 by Miraa Higgins: "40.00 Set 1/4 Sec Post. Y. Birch 15 N65E 7, Sugar 10 S30W 21". Found no subsequent record.

(E5) Corner common to Sections 8-9-16-17. Established in 1846 by Miraa Higgins: "80.00 Set post cor 8,9,16,17... Hemlock 36 N65E 26, do 20 S70W 31". 1981 Vulcan Corporation records show corner monumented by a red iron pipe at the intersection of blue paint lines, and witnessed by an aluminum tag and a 12" hemlock.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) Original post and accessories not recovered. Remonumented the corner according to the original record distance north from the Section Corner common to Sections 17-18-19-20. An index correction of +0.531 ch/40 ch. was applied to this distance. The index was a mean correction observed on 6 line segments in this area of the township. The original survey contains an error in this mile, it measuring 4.946 ch. longer than record. Based on a similar discrepancy on the line between Sections 16-17, I concluded the error belonged in the North 1/2 mile of this line and so placed it there. From this position, original stream call to the south checks with the record. At the position for the corner, I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet appropriately stamped. The corner falls at the intersection of blue paint lines North, East, and West.

(E5) Original post and accessories not recovered. Found a 1 1/2" iron pipe with aluminum Vulcan location poster on a 12" hemlock facing. Also found a 20" cedar signature tree facing the pipe S54W 17.0' distant. Possible remains of the 36" Hemlock BT, now a large rotted hemlock stump with no markings evident is at record bearing and distance from the pipe. Distance West to a similar pipe checks with the original record. Distance south to monumented 1/4 corner was found to be 6.56 chains longer than record. I accepted the pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following new bearing trees:

16" Sugar N25E 11.4' "1/4S NBT"
 10" Sugar N59W 27.3' "1/4S NBT"
 12" Maple S35W 28.1' "1/4S NBT"
 7" Maple S45E 38.5' "1/4S NBT"

Set a squared 4" sugar post adjacent.
 Bearings are magnetic.

(E5) Found 1 1/2" iron pipe.
 Blazed and scribed the following new bearing trees:

7" Hemlock S33E 15.3' "S16 NBT"
 12" Maple S35W 18.5' "S17 NBT"
 12" Hemlock N29W 21.0' "S8 NBT"
 12" Maple N26E 14.6' "S9 NBT"

Bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Stephan J. Szyszkoski Date 10-26-95

Surveyor's Michigan License No. 33986

