

40

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Houghton

	(County)	Located In:	Corner Code $\neq$
1. Public Land Survey		T <u>52N</u> R <u>36W</u>	<u>E7</u>
		T <u>52N</u> R <u>36W</u>	<u>C7</u>
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on October 23, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(E7) Corner common to Sections 16-17-20-21. Established in 1846 by Hiram Higgins: "80.00 Set Post Cor Sec 16,17,20,21...Hemlock 36 N35W 25, Ironwood 8 S50E 28". Mead records dated Sept. 12, 1967 and Nov. 30, 1983 state: "2" iron pipe 8" above ground. Yellow tag on 13" elm N12E 15 ft. to cor., 7.7" Hard Maple (Beaver) N48W 9 ft. to cor., 6.9" Hard Maple (Beaver) S12W 6 ft. to cor. Yellow tag on Poyhnen log rd. app. 11.5 ch. E to cor".

(C7) Corner common to Sections 17-18-19-20. Established in 1846 by Hiram Higgins: "80.00 Set Post Cor. Sec. 17,18,19,20...Sugar 15 N65E 50, do 12 S80W 15". Mead records dated 11/19/84 state "1 1/2" iron pipe 2' above ground. 7" Sugar Maple S51E 14.1', 11" Bass N02W 11.3', 10" Elm N40W 8.1'".

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(E7) Original post and accessories not recovered. Found a 1 1/2" dia. iron pipe at record bearing and distance from the Elm noted in the Mead record. The Elm is now down. The other Mead witnesses were not recovered. Distances north and west to monumented 1/4 corners check well with the original record. I accepted the pipe as the best available evidence of the position of the original corner.

(C7) Original post and accessories not recovered. Found a 1 1/2" iron pipe in accord with Meads remaining Elm witness, now dead. The other two trees were not to be found. Found a Copper Range location poster on a 7" Sugar facing the pipe. Distances East and West to monumented 1/4 corners are +0.52 ch. and +0.74 ch. respectively. I observed a similar overage on several other lines in this area of the township. Distance North to stream at 19.50 chains checks with the original record. I accepted the pipe as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(E7) Found 1 1/2" iron pipe.  
Blazed and scribed the following new bearing trees:  
8" Sugar S48E 8.2' "S21 NBT"  
7" Sugar N19E 19.0' "S16 NBT"  
10" Sugar S33W 24.2' "S20 NBT"  
4" Ironwood N39W 11.3' "S17 NBT"  
Bearings are magnetic.

(C7) Found 1 1/2" iron pipe.  
Blazed and scribed the following new bearing trees:  
5" Y. Birch S73E 10.3' "S20 NBT"  
6" Sugar N56E 29.4' "S17 NBT"  
7" Sugar N67W 17.8' "S18 NBT"  
5" Sugar S55W 17.5' "S19 NBT"  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10-26-95

Surveyor's Michigan License No. 33986