

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

(County)

Located In:

Corner Code ##

1. Public Land Survey	T <u>52N</u> R <u>36W</u>	<u>B7</u>
	T <u>52N</u> R <u>36W</u>	<u>A6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on A6 October 12, 1995 and B7 October 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B7) Quarter corner common to Sections 18-19. Corner established in 1846 by Hiram Higgins: "40.20 Set 1/4 Sec. post. Sugar 10 N75E 17, do 10 S40W 13. 1966 Mead records show: "1 1/2" iron pipe, Yellow tag on 9" Hard Maple (Beaver) N09E 12', 6" Ash (Beaver) S66W 9', 8" Basswood(Beaver) S41E 20'".

(A6) Quarter corner common to Section 18 T52N-R36W and Section 13 T52N-R37W. Established in 1845 by Wm A. Burt: "40.00 Set qr Section post. Hemlock 12 S27W 37, do 16 N30W 28". Mead records dated Jan 24, 1966 state: 4" Ash post at corner Old Hemlock stump (B.T.) N26W 17 ft., 8" Hard Maple (Beaver) S24W 9 ft". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B7) Original post and accessories not recovered. Found a 1 1/2" iron pipe marking the corner in accord with the 1966 Mead hard maple witness to the NE. Distance East to monumented Section corner is 0.74 ch. longer than record. Distance west to Section corner on Range line is 1.37 ch. shorter than record and I observed a 3 deg. 42 min. right deflection in the section line at this corner. I accepted the pipe as the best available evidence of the position of the original corner.

(A6) Original post not recovered. Mead's Ash post was not recovered. Re-monumented the corner at record bearing and distance from the remains of the original bearing trees. The Hemlock NW was recovered as a rotted stump of proper size and species. No markings were found. A distinct stump hole marks the location of the other Hemlock BT. The corner is also in accord with Mead's 8" Maple, recovered as described. Also, An old unreadable location poster, possibly by Copper Range, faces the corner on a 14" Sugar. A dead 4" squared Sugar was found adjacent. Distances North and South to adjacent Section corners are -0.06 ch. and +0.32 ch. respectively, compared to the original record. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B7) Found 1 1/2" iron pipe.

Blazed and scribed the following new bearing trees:

5" Sugar N75E 10.9' "1/4S NBT"

6" Maple S25E 15.1' "1/4S NBT"

found with blazes and a beaver.

10" Ash S68W 10.8' "1/4S NBT"

found with blazes.

12" Maple N16E 12.4' "1/4S NBT" with

blazes and location poster.

Bearings are magnetic.

(A6) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following new bearing trees:

14" Sugar N08W 26.6' "1/4S NBT"

15" Maple N47E 10.1' "1/4S NBT"

10" Sugar S20E 3.7' "1/4S NBT"

8" Sugar N80W 17.6' "1/4S NBT"

Bearings are magnetic. Placed a 3"

squared ash post adjacent.



Signed by

Stephan J. Szyszkoski

Date

10-26-95

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division