

38.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Houghton <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>36W</u>	<u>07</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on October 23, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(07) Quarter corner common to Sections 17-20. Established in 1846 by Hiram Higgins: "40.01 Set 1/4 Sec Post. Ironwood 8 N35W 6, Sugar 12 S50E 29". 1984 Mead records state: "1 1/2" iron pipe 12" above ground. Yellow tag on 8.5" Sugar Maple S13E 13.0' to cor., 10.0" Bass S56W 5.4' to cor., 15.6" Sugar Maple N30W 3.3' to cor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(07) Original post and accessories not recovered. Found a 1 1/2" dia. iron pipe in accord with Maple N30W, above. Distances East and West to adjacent Section corners are 0.489 and 0.524 ch. longer than record, respectively. The pipe is 5.2' north of a straight line between these two corners. I accepted the pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(07) Found 1 1/2" iron pipe.
 Blazed and scribed the following new bearing trees:

16" Sugar S28E 2.5'	"1/4S NBT"
7" Sugar W29E 14.0'	"1/4S NBT"
8" Sugar S41W 23.4'	"1/4S NBT"
7" Sugar N52W 20.1'	"1/4S NBT"

Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10-26-95
 Surveyor's Michigan License No. 33986