

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

(County)

Located In:

Corner Code ≠#

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>52N</u> R <u>36W</u> | <u>K11</u> |
| | T _____ | _____ |
| | T _____ | _____ |
| | T _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on May 12, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K11) Corner common to Sections 25-26-35-36. Corner re-monumented at the position of the original corner as determined from the original Hemlock bearing tree S30E, 63 links, in 1964 by Billy D. Buckler, ALS. The corner position was found marked with an iron pipe, which was replaced with a 1" iron pipe capped with a 4" cast aluminum Michigan Dept. of Conservation tablet. Buckler marked the following new witnesses: 12" N. Pine N47E 37 links, 10" Cedar N52W 47 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K11) Recovered the 1964 monument, in good condition, as described, at substantially record bearing and distance from the 2 1964 NBTs. The bearing to the White pine was observed to be N54E. Both trees are in good condition and have increased 6" in diameter. Left the monument in place and marked two new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K11) Found 1" iron pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees:
 5" Hemlock S38W 23.6' "S35 NBT"
 24" Hemlock S42E 38.6' "S36 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 3-7-95
 Surveyor's Michigan License No. 33986