

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 1998

Nov 6 1998
Robert W. Carpio

SECTION

Houghton County Located in: Corner Code #

1. Public Land Survey T53N R32W C4
T53N R32W C3
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

ROBERT F. MIKESCH 11/11/98
HOUGHTON COUNTY, REGISTER 09:41
LC 3/ 522 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3			●										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Steven C. Hein, in a field survey on September 4, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C4: W1/4 Corner Section 8: From original notes: South between Sections 7 & 8; 40.00 Set qr. Section post; Hemlock 16 S65E 16; Do 12 N64W 13. No evidence of original corner or accessories

C3: Northwest Corner Section 8: From original notes: South between Sections 5 & 6; 80.00 Set post corner of Sections 5, 6, 7 & 8; Tamarack 14 S80W 35; Fir 10 N50E 04. No evidence of original corner or accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C4: W1/4 Corner Section 8: Found 5/8" pipe in 8" cylinder of concrete encased on sewer pipe, 6" B.G.; Concrete scribed with "1/4" and "S" and copper tag with "347 WWS" inbedded in concrete. Corner set by W. W. Stockley around 1920. No apparent witnesses found. Found 1 1/2" pipe bears N78°E 8.3'. Fences N, S, E & W intersect at 13' Birch with location poster

C3: Northwest Corner Section 8: Found 5/8" pipe in 8" cylinder of concrete (top of conc. Broken and top of pipe bent) Cut pipe at straight point, 9" below gravel road surface, 6.5' North of County Road centerline. Corner set by W. W. Stockley around 1920. No apparent witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C4: Set 2 1/4" Brass Cap within found pipe in concrete, dug hole around corner	C3: Set 2 1/4" Brass Cap within found pipe in concrete, 9" below gravel road surface
Witnesses:	Witnesses:
13" Birch N79°E 10.54'	7" Balsam N29°E 38.28'
6" Cedar S35°E 17.92'	6" Cedar S32°E 50.32'
7" Cedar S43°W 14.63'	6" Cedar w/ loc. poster S02°E 46.76'
7" spruce N49°W 34.65'	8" Balsam N36°W 39.39'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein

Date Oct. 31, 1998

Surveyor's Michigan License No. 32336