

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 1998

SECTION

Nov. 6, 1998
 Robert W. Campbell

For corners in

Houghton County Located in: Corner Code #

1. Public Land Survey T53N R32W MC C5-D5 Z4
 T53N R32W C5
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. , Recorded Plat
 5. Private Claims

ROBERT F. MIKESCH 11/11/98
 HOUGHTON COUNTY, REGISTER 09:41
 LC 3/ 521 PAU Fee: 9.00
 Page 1 of 1

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Steven C. Hein, in a field survey on September 4, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MC C5-D5 Z4: From original notes: East between Sections 8 & 17; 38.72 Intersected Keweenaw Bay. Set Meander post on ledge of sand rock about 70 feet high; fir 6 S71W 21; Cedar 8 N30W 17. No evidence of original corner or accessories.

C5: Southwest Corner Section 8: From original notes: South between Sections 7 & 8; 80.00 Set post corner of Sections 7, 8, 17 & 18; Hemlock 14 N12E 25; Fir 12 S14W 43. No evidence of original corner or accessories found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MC C5-D5 Z4: Found 1" pin, 13" A.G., 26' East to top of sandstone ledge. Fence line to West. Pin fits well with undated survey within Section 17, T53N-R32W by Steinhilb & Hesterberg. Recovered and used personally in a 1997 survey.

C5: Southwest Corner Section 8: Found 1/2" pipe in 9" cylinder of concrete, 6" B.G., 3.5' Easterly of centerline drive to fire # J-24, as recorded in Liber 2 of L.C.R.C., page 631. Witnesses of said record: 12" Spruce N30°W 24.18'; 8" Spruce S85°E 105.71'; 12" Spruce S4°E 93.09'; Util. Pole S34°W 44.18'; 1/2" rod in monument East 77.70'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MC C5-D5 Z4: Set 2 1/4" Brass Cap
 On 3/4" pipe, 26' East to ledge
 Location poster on 7" Cedar to SW.
 Witnesses:
 12" H. Maple N85°E 7.03'
 5" Cedar S02°W 18.49'
 7" Cedar S58°W 7.82'
 6" Cedar N49°W 4.32'

C5: Set 2 1/4" Brass Cap within found
 pipe in concrete, 6" B.G.
 Witnesses (check):
 14" Spruce N30°W 24.07'
 8" Spruce S85°E 105.77'
 12" Spruce S40°E 93.02'
 Util. Pole S34°W 44.20'
 1/2" rod in monument East 77.70'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein
 Surveyor's Michigan License No. 32336

Date Oct. 31, 1998