

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 1998

SECTION

Nov. 6, 1998
Robert W. Campbell
For corners in

| | | |
|---------------------------------------|--------------------------------------|-------------------|
| Houghton County | Located in: | Corner Code # |
| 1. Public Land Survey | T53N R32W T53N R32W T R T R | MC C6-C7 Z5 C6 |
| 2. Property Controlling in Section | S T R S T R | |
| 3. Miscellaneous Property in Sec. | S T R S T R | |
| 4. Lot No. | Recorded Plat | |
| 5. Private Claims | | |

ROBERT F. MIKESCH 11/11/98
HOUGHTON COUNTY, REGISTER 09:41
LC 3/ 520 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, Steven C. Hein, in a field survey on September 4, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MC C6-C7 Z5: From original notes: South between Sections 17 & 18; 67.40 Intersected Keweenaw Bay; Spruce 12 for Meander Corner of perpendicular ledge of sand rock about 55 feet high; Spruce 12 N70W 08. No evidence of original corner or accessories found.

C6: W1/4 Corner Section 17: From original notes: South between Sections 17 & 18; 40.00 Set qr. Section post; Y. Birch 12 N36E 20; Do 8 S64W 21. No evidence of original corner or accessories found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MC C6-C7 Z5: Found fence post at top of sandstone ledge which fits well with line extended from the Northwest corner of Section 17 through the West Quarter corner of Section 17. Set corner at safe distance North from top of ledge.

C6: W1/4 Corner Section 17: Found 1" square pin 4 feet West of centerline of Co. Rd. T-29 as recorded in Liber 2 of L.C.R.C., page 667. Witnesses of said record: Util. Pole N19°E 101.27'; 18" Spruce S83°E 33.76'; 15" Maple S48°W 55.66'; N86°W 16.80' to a 1" bolt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|---|---|
| MC C6-C7 Z5: Set 2 1/4" Brass Cap On 3/4" pipe, 46' So. To ledge, 38' NW'ly. to centerline County Road Witnesses: 6" Balsam N41°E 5.33' 6" Cedar S39°E 8.72' 10" Spruce S48°W 22.65' 13" Spruce N11°W 23.88' | C6: Set 2 1/4" Brass Cap on 3/4" pipe 13" below gravel road surface Witnesses (check): Util. Pole N16°E 101.14' 20" Spruce S83°E 33.71' 16" Maple S48°W 55.57' 1" Bolt N89°23'09"W 16.78' New Witness: 6" Cedar N50°E 47.95' |
|---|---|



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by Steven C. Hein Date Oct. 31, 1998
Surveyor's Michigan License No. 32336