

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. <u>53</u> N. S., R. <u>32</u> E. W.	<u>4, 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 26, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 4: Found 1" sq. iron rod in concrete set by William W. Stockly on section subdivision.
- Corner 15: Found 1/2" iron pipe in concrete set by William W. Stockly on section subdivision.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 4: Re-established at 1" sq. iron rod.
- Corner 15: Re-established at monument. Fits good with original field notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner 4: 1" sq. Iron Rod in concrete.
 - 16" Sugar N15W 16.9 ft. 1/16 S,BT
 - 8" Cedar S13W 30.9 ft. 1/16S, BT
 - 10" Maple N81E 23.9 ft. 1/16S,BT
- Corner 15: 1/2" Iron Pipe in concrete nail and DNR tag in:
 - 5" aspen S66E 1.95 ft.
 - 9" Twin Maple S62W 13.13 ft.
- Corner falls on edge of old hay field at edge of drop off to east.

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 30, 1978

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006