

Houghton Co.

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 53 N. R. 32 W.	E3, E2
2. PROPERTY CONTROLLING IN SECTION	4, T. 53 N. R. 32 W.	8
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 20, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior. Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on July 20, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner E3: Original Monument and Accessories Not Found. Found 1" O.D. Pipe in concrete buried in County Road. This monument set by William W. Stockly.
- Corner E2: Original Monument and Accessories Not Found. Found 1" O.D. pipe in concrete buried in county road. This monument set by William W. Stockly.
- Corner 8: Found 1" O.D. pipe in concrete buried in old road. This corner set by William W. Stockly on section subdivision.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner E3: Re-established at monument.
- Corner E2: Re-established at monument.
- Corner 8: Re-established at monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| <ul style="list-style-type: none"> <li>Corner E3: 1" O.D. iron pipe in concrete.</li> <li>Nail and DNR reference tag in power pole N54E 41.25 ft.</li> <li>Nail and DNR reference tag in power pole S12W 136.20 ft.</li> <li>Underground cable marker N49W 40.0 ft.</li> <li>Corner E2: 1" O.D. iron pipe in concrete.</li> <li>Nail &amp; DNR reference tag in 6" piplar S30E 60.05 ft.</li> <li>Nail &amp; DNR reference tag in power pole N45E 40.20 ft.</li> <li>Nail &amp; DNR reference tag in 5" aspen S50W 45.58 ft.</li> </ul> | <ul style="list-style-type: none"> <li>Corner 8: 1" O.D. iron pipe in concrete raised with 1" I.D. x 24" iron pipe with 4" aluminum cap. Nail and DNR reference tag in:</li> <li>7" Sugar S26W 26.18 ft.</li> <li>3" Yellow Birch S57E 31.40 ft.</li> <li>3" Maple N09W 35.90 ft.</li> </ul> |
|---|--|

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 30, 1978

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
Keith L. Sackett  
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

