

Houghton Co

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>53</u> N. <u>X</u> , R. <u>32</u> E. <u>W.</u>	<u>F2</u>
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	, T. <u>53</u> N. <u>X</u> , R. <u>32</u> E. <u>W.</u>	<u>M.C Between F2 &amp; G2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 26, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F2: Not Set on Original Survey. Section was subdivided by W. W. Stockly.  
 Corner MC: Not Set on Original Survey Nor Subsequently Apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F2: Unable to find any trace of corner. Section was subdivided by W. W. Stockly. Restored corner on line and double the distance from Stockly's west 1/4 corner to Stockly's west 1/16 on east-west 1/4 line.  
 Corner MC: Established on line projected from west 1/4 corner through center 1/4 corner at bank on shore of Lake Superior.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner F2: 1" I.D. x 36" Iron Pipe with 4" aluminum cap.	Corner MC: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap.
5" Cedar N15E 8.8 ft. 1/4S,BT	13" Maple N60W 3.2 ft. MC,BT
7" Cedar West 56.8 ft. 1/4S,BT	10" Cedar N09W 19.3 ft. MC,BT
4" B. Ash S25E 4.9 ft. 1/4S,BT	5" Balsam N38E 15.2 ft. MC,BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE October 30, 1978  
 CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

