

April 30, 1999  
Robert W. Crampton

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

SEP 17 1999

For corners in  
HOUGHTON  
(County)

Located In:

Corner Code #

SECTION

- 1. Public Land Survey T 53N R 33W TL K-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

MARY SCHOOS 05/04/99 2  
HOUGHTON COUNTY, REGISTER 11:04  
LC 3/ 583 PAU Fee: 9.00  
Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R.W. CRAMPTON, in a field survey on OCTOBER 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*K-3, SET POST CORNER SECTIONS 1, 2, 11 & 12, W. PINE 26 N80E 156, W. BIRCH 6, S22W 95.*



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*K-3, SET 1/4" IRON PIPE WITH 2 1/4" BRASS CAP ON A LINE FROM THE NORTH 1/4 CORNER OF SECTION 12 TO THE NW 1/16 CORNER (2" IRON PIPE FND), EXTENDED WEST AND THE A LINE FROM THE MEANDER CORNER ON SOUTH SIDE OF PORTAGE CANAL ON THE WEST LINE OF SECTION 12 AND A 5/8" IRON PIN IN FENCE LINE, ON WEST LINE OF SECTION 12, (S01°53'20"E 573.61' FROM 1 1/4" IRON PIPE WITH BRASS CAP) EXTENDED NORTH. CORNER 50' INTO SWAMP.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*K-3, THE 1 1/4" IRON PIPE WITH BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:  
12" CEDAR TREE S66°E 57.40', 5" MAPLE TREE S30°E 50.68',  
12" SPRUCE TREE S05°W 54.59', 14" W. BIRCH TREE S41°W 91.05'.*

Signed by Robert W. Crampton

Date MARCH 22, 1999

Surveyor's Michigan License No. 24591