

SURVEY
RECORDS
MONUMENTATION

Robert W. Crampton
Nov. 6, 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 1998

For corners in HOUGHTON
(County)

Located In: _____ Corner Code # _____

SECTION _____

- 1. Public Land Survey T 53W R 33W K-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

Seq. #2

ROBERT F. MIKESCH 11/16/98
HOUGHTON COUNTY, REGISTER 14:44
LC 3/ 540 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, R. W. CRAMPTON, in a field survey on OCTOBER 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

*K-7, SECTION CORNER COMMON TO 13, 14, 23 AND 24
SET POST, BEARING TREES: FIR 7" N64°W 30 LINKS, YELLOW BIRCH 7" S40°E 8 LINKS*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7, FOUND 3/4" PIPE 2 FEET BELOW ROAD GRADE, 6 INCHES SOUTH OF CENTERLINE OF COUNTY ROAD. CORNER REFERRED TO ON MAP DRAWN BY H. W. FESING, R.L.S. AND IN FIELD NOTES DATED AUGUST, 1943. PREVIOUSLY RECORDED IN LIBER 1, PAGE 673, BY H.L. O'DONNELL, NOV. 19, 1981.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7, REPLACED 1/2" REBAR WITH 1 1/4" IRON PIPE WITH 2 1/4" BRASS CAP, 6" BELOW ROAD GRADE. ESTABLISHED NEW BEARING TREES: CEDAR 7" S32°E 42.48', POPLAR 12" N34°W 55.18', POPLAR 9" N35°E 46.88', 4" MAPLE N07°E 36.60'.

Signed by *Robert W. Crampton*

Date NOVEMBER 4, 1998

Surveyor's Michigan License No. 24591