

SEP 17 1999

APRIL 30, 1999
Robert W. Crampton

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
HOUGHTON
(County)

Located In:

Corner Code #

SECTION

- 1. Public Land Survey T 53N R 33W TL MEANDER-11 1/4 Seg. 2
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

MARY SCHOOS 05/04/99 2
HOUGHTON COUNTY, REGISTER 11:05
LC 3/ 584 PAU Fee: 9.00
Page 1 of 1

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, R.W. CRAMPTON, in a field survey on OCTOBER 5, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MEANDER-11 SET MEANDER POST ON RIGHT BANK IN MARCH NO BEARING TREE



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MEANDER-11, SET 1 1/4" IRON PIPE WITH 2 1/4" BRASS CAP ON LINE BETWEEN THE MEANDER CORNER ON THE SOUTH SIDE OF PORTAGE CANAL AND A 5/8" IRON ROD IN OLD FENCE LINE ON W LINE OF SECTION 12, S01°53'30"E 573.61' FROM NW CORNER OF SECTION 12, 64' TO WATER'S EDGE, 53' TO WEST OLD FENCE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*MEANDER-11 THE 1 1/4" IRON PIPE WITH BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
24" PINE TREE N69°W 35.44', 12" MAPLE TREE N67°E 62.20',
10" MAPLE TREE S66°E 54.71', 30" PINE TREE S26°W 35.54'.*

Signed by *Robert W. Crampton*
Surveyor's Michigan License No. 24591

Date MARCH 22, 1999