

Robert W. Crampton
APRIL 30, 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

SEP 17 1999

For corners in
HOUGHTON
(County)

Located In: Corner Code #

1. Public Land Survey

T 53N R 33W

MEANDER-15 4/15 *Seg. 2*

SECTION

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Section

S _____ T _____ R _____

S _____ T _____ R _____

MARY SCHOOS 05/04/99 2
HOUGHTON COUNTY, REGISTER 11:06
LC 3/ 585 PAU Fee: 9.00
Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R.W. CRAMPTON, in a field survey on OCTOBER 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MEANDER-15 NOT SET IN ORIGINAL SURVEY



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MEANDER-15, SET 1 1/4" IRON PIPE WITH 2 1/4" BRASS CAP ON LINE BETWEEN 1/4 CORNER BETWEEN SECTIONS 12 AND 13, T53N, R33W AND THE COMPUTED CORNER OF SECTIONS 12 AND 13, T53N, R33W, AND SECTIONS 7 AND 18, T53N, R32W. WHICH WAS COMPUTED BY USING THE W 1/4 CORNER OF SECTION 13, AS SHOWN ON THE UNRECORDED PLAT OF PORTAGE VIEW LOTS AND THE NORTH 1/4 CORNER OF SECTION 18, T53N, R32W AND THE ABOVE STATED UNRECORDED PLAT AT EDGE OF LARGE SWAMP. N89°44'07"E 729.70' FROM THE 1/4 CORNER BETWEEN SECTIONS 12 AND 13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*MEANDER-15 THE 1 1/4" IRON PIPE WITH BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
6" W. BIRCH TREE N69°W 9.53', 5" W. BIRCH TREE N22°E 12.94',
6" BALSAM TREE N73°E 11.21', 16" POPLAR TREE S02°W 11.73'.*

Signed by *Robert W. Crampton*

Date MARCH 22, 1999

Surveyor's Michigan License No. 24591