

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 33 W


PORTAGE RIVER ACCESS SITE Houghton COUNTY

DESCRIPTION OF CORNER Center Corner, Section 12

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/9/65 Distances in Feet

WITNESSES TO CORNER..... 9" Soft Maple (B^m), N 79° E, 13.5'



7" Cedar (B^m), N 03° E, 22.9'

8" Cedar (B^m), S 55° W, 32.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner replaced at an old Cedar Post lying 3' North of an old wire fence. Found a W. Spruce 10' East of Corner having blazes marked about 1940 and 1921. Age determined by count of annual growth rings. Found a new Wood Post West set by unknown persons.

SURVEYOR'S SEAL

Billy D. Buckler.
SIGNED Billy D. Buckler DATE 3/24/1966
REGISTERED LAND SURVEYOR