

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 53 ^{N.} S. , R. 33 ^{W.} E.	H-11, I-11, G-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S., R. _____, E., W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S., R. _____, E., W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner H-11: Original monument and accessories not found. Found 1" I.D. iron pipe of unknown length buried in road intersection - roads N-S and E-W.
- Corner I-11: Original monument and accessories not found. Found 1/2" rebar buried in county road in line with fence north and roads east, west and south.
- Corner G-11: Original monument and accessories not found. Found old scribed post - believe to have been set by P. A. Larsen in early 1920's.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner H-11: Re-established 2/11/77 at iron pipe.
- Corner I-11: Re-established 3/28/77 at rebar.
- Corner G-11: Re-established 4/18/77 at old post location. Fits good with other corners in the area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <p><u>Corner H-11:</u> 1" I.D. iron pipe of unknown length.</p> <p>Nail in 16" spruce S37°E 55.6'</p> <p>Nail in power pole S52°W 43.6'</p> <p>Nail in power pole N45°W 43.3'</p> | <p><u>Corner G-11:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>14" cedar N35°W 11.2' S28 NBT</p> <p>4" cedar N41E 21.2' S27 NBT</p> <p>6" cedar S42E 17.3' S34 NBT</p> |
|---|---|
- Corner I-11: 1/2" rebar by unknown length.
- NE garage corner S13°W 34.0'
- NW garage corner S39°E 48.0'
- Telephone junction box N28°W 37.7'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

