

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 53 <sup>N.</sup> <sub>X.</sub> R. 33 <sup>X.</sup> <sub>W.</sub>	G-9
2. PROPERTY CONTROLLING IN SECTION _____	T. 53 <sup>N.</sup> <sub>X.</sub> R. 33 <sup>X.</sup> <sub>W.</sub>	2, 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> <sub>S.</sub> R. _____ <sup>E.</sup> <sub>W.</sub>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner G-9: Original monument and accessories not found. Found old post by P. A. Larsen set prior to 1920.
- Corner 2: Not set on original survey. Found old post by P. A. Larsen set prior to 1920.
- Corner 16: Not set on original survey. Found old scribed post believed to have been set by P. A. Larsen prior to 1920.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner G-9: Re-established 5/3/77 at old post location. Corner fits good with other corners in the area.
- Corner 2: Re-established 5/3/77 at old post location. Fits good with other corners in area.
- Corner 16: Re-established 4/25/77 at old scribed post. Fits good with other corners in area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner G-9: 1" I.D. x 36" iron pipe with 4" aluminum cap.
  - 6" Sugar N49°W 43.7' S21 NBT
  - 9" Sugar S41°E 52.1' S27 NBT
  - 6" Sugar N84°E 20.1' S22 NBT
- Corner 2: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
  - 7" Cedar N70°E 32.1' 1/16S BT
  - 8" Tamarack S49°E 16.4' 1/16S BT
  - 10" Spruce S86°W 13.2' 1/16S BT
- Corner 16: Set 1" I.D. x 36" iron pipe with 4" aluminum cap. Corner is in tag alder swamp. Nothing in area for witnesses.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977  
CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

