

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--:                            | LOCATED IN--:   | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____                  | T. <u>53</u> <sup>N.</sup> <del>X.</del> R. <u>33</u> <sup>X.</sup> <del>W.</del> | <u>A-9, C-11</u>   |
| 2. PROPERTY CONTROLLING IN SECTION <u>29</u> | T. <u>53</u> <sup>N.</sup> <del>X.</del> R. <u>33</u> <sup>X.</sup> <del>W.</del> | <u>1</u>           |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____   | T. _____ <sup>N.</sup> <del>S.</del> R. _____ <sup>E.</sup> <del>W.</del>         | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____        |   |                    |
| 5. PRIVATE CLAIMS _____                      |   |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner A-9: Original monument and accessories not found. Found 1" I.D. x unknown length iron pipe. Has been used by local property owners for years. Fits good with the other corners in the area.
  - Corner C-11: Original monument and accessories not found. Found old post in north-south fence line. Post pointed out by M. C. Larsen.
  - Corner 1: Not set on original survey nor subsequently apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner A-9: Re-established 7/21/77 at iron pipe.
  - Corner C-11: Re-established 7/22/77 at posted location.
  - Corner 1: Established 7/22/77 on line between corners east and west.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner A-9: 1" I.D. x unknown length iron pipe buried in driveway.
 

|                        |       |       |  |
|------------------------|-------|-------|--|
| Nail in power pole     | S61°W | 37.6' |  |
| NW garage corner       | S84°E | 24.8' |  |
| Telephone junction box | N48°E | 40.9' |  |
  - Corner C-11: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 

|                          |       |        |          |
|--------------------------|-------|--------|----------|
| 24" Sugar                | S19°E | 104.4' | S32, NBT |
| North gate corner post   | S     | 1'     |          |
| N-S-W fence corner north |       | 78.5'  |          |
  - Corner 1: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 

|           |       |       |           |
|-----------|-------|-------|-----------|
| 16" Maple | N08°E | 17.7' | 1/16S, BT |
| 8" Maple  | S84°W | 3.1'  | 1/16S, BT |
| 12" Elm   | S53°E | 28.6' | 1/16S, BT |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

