

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 53 <sup>N.</sup> / <sub>S.</sub> , R. 33 <sup>E.</sup> / <sub>W.</sub>	A-11, A-12, A-10
2. PROPERTY CONTROLLING IN SECTION <u>31</u>	T. 53 <sup>N.</sup> / <sub>S.</sub> , R. 33 <sup>E.</sup> / <sub>W.</sub>	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> / <sub>S.</sub> , R. _____ <sup>E.</sup> / <sub>W.</sub>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner A-11: Original monument and accessories not found. We found 15" squared maple S79°E, 37', placed by unknown person(s).  
Corner A-12: Original monument and accessories not found.  
Corner A-10: Original monument and accessories not found.  
Corner 10: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner A-11: Re-established 7/18/77 on line between corners north and south.  
Corner A-12: Re-established 7/19/77 on line between corners north and south.  
Corner A-10: Re-established 7/20/77 on line between corners north and south.  
Corner 10: Established 7/19/77 on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |
|---|---|
| <p><u>Corner A-11:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.<br/>                 8" Maple N36°E 22.6' S30 NBT<br/>                 14" Sugar S05°W 26.4' S36 NBT<br/>                 5" Maple N43°W 9.5' S25, NBT</p>   | <p><u>Corner A-10:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.<br/>                 6" Maple S85°W 4.8' ¼S, NBT<br/>                 7" Maple South 6.4' ¼S, NBT<br/>                 7" Maple N42°E 16.5' ¼S, NBT</p>  |
| <p><u>Corner A-12:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.<br/>                 8" Y. Birch S77°W 17.8' ¼S, NBT<br/>                 12" Maple S61°E 7.8' ¼S, NBT<br/>                 8" Maple N54°E 12.4' ¼S, NBT</p> | <p><u>Corner 10:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.<br/>                 11" Maple N80°W 5.1' 1/16S BT<br/>                 6" Maple S15E 12.7' 1/16S BT<br/>                 9" Maple N04E 21.3' 1/16S BT</p> |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
 REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET

