

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T 53 N. R. 33 X. W.	H-11, I-11
2. PROPERTY CONTROLLING IN SECTION.....	T..... N. S., R. .... E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T..... N. S., R. .... E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were in a field survey on see below 19\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner H-11: Original monument and accessories not found.  
Found 1" I.D. iron pipe of unknown length buried in N-S-E-W road intersection.
- Corner I-11: Original monument and accessories not found.  
Found ½" re-bar buried in county road in line with fence north and roads east-west and south.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner H-11: Reestablished 2/11/77 at pipe.  
Corner I-11: Reestablished 3/28/77 at ½" re-bar.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Corner H-11: 1" I.D. x unknown length iron pipe.  
Nail in 16" Spruce S37°E 55.6'  
" " power pole S52°W 43.6'  
" " " " N45°W 43.3'
- Corner I-11: ½" x unknown length re-bar buried in county road.  
NE garage corner S13W 34.0 ft.  
NW garage corner S39E 48.0 ft.  
Telephone junction box N28W 37.7 ft.


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett MICHIGAN REGISTERED LAND SURVEYOR DATE 4/18/77  
Keith L. Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006