

Houghton Co.

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 53 N. 33 W. G10
2. PROPERTY CONTROLLING IN SECTION 28, T. 53 N. 33 W. 14
3. MISCELLANEOUS PROPERTY IN SECTION... T. N. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 24, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G10: Original Monument and Accessories Not Found. Found old scribed post set around 1920 pointed out by Paul Tapio long time local resident.
Corner 14: Found old 3" Iron Pipe.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G10: Restored at post.
Corner 14: Re-established at pipe. Pipe pointed out by Paul Tapio, long time local resident who has used pipe as corner for over 40 years.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G10: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap in east-west fence line. 10" Sugar N35W 38.0 ft. 1/4 S, NBT
Corner 14: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap. Power pole N25E 60.5 ft. Underground telephone wire location iron S68W 13.6 ft. Fence corner west 12.6 ft.

SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY DATE

APPROVED AND SIGNED BY DATE

CHIEF OF SURVEY PARTY
Keith L. Sackett
MICHIGAN REGISTERED LAND SURVEYOR
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006