## LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -: LOCATED IN -: CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY T. 53N S., R. 33W W. D11	
2. PROPERTY CONTROLL: 29 ,T. 53N N. 33W E. 9, 16	
3. MISCELLANEOUS N. E. PROPERTY IN SECTION, T	
4. LOT NO, RECORDED PLAT	
5. PRIVATE CLAIMS	REGISTER OF DEEDS STAMP AND FILING NUMBER
I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines I and 2 above were, in a field survey on March 6, 19_79, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:  A. Description of original monument and accessories and/or subsequent restoration:  Corner 01: Original monument and accessories not found. Found old axe marks in area.  Corner 9: Not set on original survey nor subsequently apparently.	
Corner 16: Not set on original survey nor subsequently apparently.  B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  Corner Dll: Restored during section subdivision. Found this location best fits with other corners in area.	
<u>Corner 9</u> : Established during section subdivision. <u>Corner 16</u> : Established on line and midway between corners eas	t and west.
C. Description of monument for corner and accessories established to perpetuate locating the Corner D11: Set 4" squared cedar post in swamp.  5" Tamarack S22°W 27.8 Ft. 1/4 S, NBT 9" Tamarack S81°E 12.5 Ft. 1/4 S, NBT 4" Maple N55°W 8.2 Ft. 1/4 S, NBT	
Corner 9: Set 1" O.D. by 4-1/2 ft. fluted iron pipe in swamp. 6" Tamarack S42°W 37.9 Ft. 1/16 S, BT 5" Tamarack N67°W 29.7 Ft. 1/16 S, BT 7" Maple N28°E 20.8 Ft. 1/16 S, BT Corner 16: Set 4" squared cedar post in tamarack swamp.	
4" Tamarack N72°W 6.7 Ft. 1/16 S, BT 6" Tamarack N75°E 10.5 Ft. 1/16 S, BT SIGNED BY 6" Tamarack S26°W 8.8 Ft. 1/16 SDARE	
SURVEYOR'S MICHIGAN REGISTRATION NO	(SEAL)
FOR STATE AND UNITED STATES AGENCIES:	THE CONTRACT OF THE PROPERTY O
SIGNED BYDATE	William Marine
APPROVED AND SIGNED BY    MICHIGAN REGISTERED LAND SURVEYOR	2/6/88 STORY 19606
SURVEYOR'S MICHIGAN REGISTRATION NO. 19006  FORM APPROVED BY MICHIGAN STATE BOAT	1000 RD OF REGISTRATION 15KN 28, 1971 HEVIDAD MAY 14, 1978