

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton

(County)

Located In:

Corner Code #

1. Public Land Survey

T 53N R 34W E3

T 53N R 34W E6

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

E6 Jul 10 2003

E3 Jul 08 2003

I, Stephan J. Szyszkoski, in a field survey on , 2003 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | ● | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | ● | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(E3) Corner common to Sections 4-5-8-9. 1846: Established by Sylvester Higgins: North between Sec. 8 & 9...80.00 Set post cor. sec. 4,5,8,9. Balsam 10 N70W 28, Hemlock 16 S25E 33. Higgins records distances: 39.95 ch. West to 1/4 corner, 79.70 ch. North to township line, 39.945 East to 1/4 corner, and 40.00 South to 1/4 corner. 1919: Notes of P.A.Larson state "Set Oct. 1904 by P.A. Larson. B.T. Hemlock 16" S25E 22' stdng. Set iron pipe in place of post. New BT Hemlock 11 N70W 28 links". Distance of 2563' East to F3 and 2679.1' South to E4 are shown.

(E6) Quarter corner common to Sections 16-17. 1846: Established by Sylvester Higgins: North between 16&17...40.00 Set 1/4 Sec. post. Balsam 6 N60W 9, Y.Birch 12 S45E 13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E3) The original post and accessories were not recovered. Found a 1.5" ID iron pipe projecting 5" above ground. Distances to West and South to found iron pipe monuments are very similar in magnitude to indexed distances observed around sections 7, 8, and 17 in this township (both are about 1/2 chain longer than record). Distance North to a 1.25" iron pipe found at the north end of a fence is 82.793 chains (3.09 chains longer than record). Measured distances East and South to F3 and E4 are 2570.06' and 2674.99', both reasonably close to Larson's considering the rough terrain in this part of the township. My survey in Section 8 did not require this corner for control. This record was prepared to provide public notice of the existence of this monument. I did not look for Larson's NBT as his notes were not in my possession at the time.

(E6) The original post and accessories were not recovered. Reestablished the corner midway between Section corners 2656.79' north and south and in the remains of a very old and broken down N-S fence line. The position for the corner is 15.02 feet West of a straight line between the section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E3) Found 1.5" dia. iron pipe. Blazed, scribed, and set measuring nails in:
 6" Maple N16W 6.1' "S5 NBT"
 9" Y.Birch S66E 9.1' "S9 NBT"
 6" Maple S43E 17.2' do
 6" Y.Birch S20W 9.5' "S8 NBT"
 Set sq'd Sugar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(E6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 6" Cherry N74E 34.1' "1/4S NBT"
 6" Cherry S64E 32.3' do
 7" Cherry S05W 43.1 do
 6" twin Cherries N25W 6.9' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/11/03