

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

(County)

Located In:

Corner Code #

1. Public Land Survey	T 53N R 34W	85
	T 53N R 34W	07
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 21 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	•											
6	18	17	16	15	14	13						
7		•										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (B5) Quarter corner common to Sections 7-18. 1846: Established by S.W.Higgins: East corrected btwn 7 & 18...39.21 Set 1/4 sec. post. Sugar 8 N57E 17, Sugar 10 S80W 13. ...79.21 Section cor.
 (D7) Quarter corner common to Sections 17-20. 1966: Billy D. Buckler RLS reestablished the corner midway and on line between Section corners. 1" pipe with aluminum cap. 40" W.Pine stump N60E 15.4', 6" W.Spruce N68W 21.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B5) The original post and accessories were not recovered. Reestablished the corner on a line of mean true bearing between Section corners 2616.05' West and 2668.76' East, being proportionate to the original record.
 (D7) Found the 1966 monument in good condition and at record bearing and distance from the 1966 witnesses. The W.Spruce is in good condition with blazes overgrown. The W.Pine stump is in poor condition. Verified the position of the corner with respect to adjacent Section corners: it is within 2.0' of the record position. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 8" Sugar N20E 5.1' "1/4S NBT" 11" Sugar S67E 17.8' do 7" Sugar S41W 20.8' do 10" Sugar West 17.6' do Set a sq'd Sugar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(D7) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in: 5" Sugar N26E 18.3' "1/4S NBT" 18" W.Pine S29W 48.1' do 4" Maple S50W 16.3' do the 1966 NBT: 10" Spruce N65W 20.6' overgrown blazes Set a sq'd Spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/23/03