

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton

(County)

Located In:

Corner Code #

1. Public Land Survey

T 53N R 34W D6

T 53N R 34W C7

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jul 17 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		9		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(D6) Center of Section 17. Not established in the original survey.

(C7) Corner common to Sections 17-18-19-20. 1966: Reestablished from local evidence by Billy D. Buckler, RLS. 1" pipe with 4" aluminum cap. 9" Soft Maple N62W 13.8', 6" Hard Maple N82E 14.0', 9" Soft Maple S74W 6.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(C7) Found the 1966 monument in good condition and at record bearing and distance from the Sugar NE and the Maple SW. The Maple NW was also found but at bearing of N36W rather than the record N62W - likely a transcription error on the 1966 LCRC. All three NBTs were in good condition though the Maple SW was cut down to facilitate GPS observations for this survey. Accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the mon. in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D6) Set 1"IDx32" I.pipe with 4" alum.

MDNR cap. Blazed, scribed, and set

measuring nails in:

5" Sugar N30E 15.95' "C1/4 BT"

7" Cherry S71E 14.0' do

8" twin Sugar (W'ly) S46W 26.7' do

(Dist. on above line is a slope dist.)

6" Sugar N19W 14.0' "C1/4 BT"

Sq'd a 8" double Sugar S31E 2.8' to

center. Bearings are magnetic.

Distances are to nail with tag.

Signed by

Surveyor's Michigan License No.

(C7) Found 1"ID I.pipe with 4" alum. MI

Dept. of Conservation cap. Blazed,

scribed, and set measuring nails in:

5" Sugar N33E 12.7' "S17 NBT"

5" Maple S27E 14.2' "S20 NBT"

The 1966 wits:

6" Sugar N86E 14.0' w/ old blaze

13" Maple N36W 13.8' do

Bearings are magnetic. Distances are to

nail with tag. Set sq'd Cedar post

adjacent.

Date



7/23/03