

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 34-35 W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 12 and 7

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5/17/61

WITNESSES TO CORNER... 10" Y. Birch (1/4s NBT) N 13° E 55½ Links



16" H. Maple (1/4s NBT) S 13° E 34 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from wood post and 3/4" Iron Rod set by unknown party. Birch, S 22° W 16" chopped out. No original marks, still standing, may be B.T. Hole in ground N 27° E, 21 Links where 16" sugar should be. Distance to corner south checks good.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 26, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler