

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 34 W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 19-30

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/1/66

WITNESSES TO CORNER..... 13" Hard Maple (1/4S NBT), N 53° E, 18.8 Feet



15" Y. Birch (1/4S NBT), S 20° E, 26.3 Feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner re-established in 19ne with Original Section Corner 1/2 mile West and a Y. Birch Line Tree 5.34 chains West. Some Hemlocks remains found in vicinity but could not identify any original evidence.

Section line to East, apparently deflects to the South about S 83° E. Similar irregularities are found in several places in this township.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR DATE 8/12/1966