

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 53 N.R. 34 W


Houghton COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 7-8-17-18

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/24/66

WITNESSES TO CORNER..... 6" Y. Birch (S7 NBT), N 12° W, 3.6 Feet



5" Soft Maple (S8 NBT), N 50° E, 42.0 Feet

6" Soft Maple (S17 NBT), S 15° E, 19.5 Feet

AND

6" Soft Maple (S18 NBT), S 25° W, 48.4 Feet

CIRCLE CORNER REGISTERED

## DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner re-established by Proportionate Measure from Corners; 1 mile West and 1/2 mile East; Streams to North and South.

Found no evidence of Original Corner or Witnesses.

Corner lies on North edge of a new Logging Road and on top of a ridge.

SURVEYOR'S SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 8/11/1966  
REGISTERED LAND SURVEYOR