

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 53 N. R. 34 W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 7-8

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/24/66

WITNESSES TO CORNER..... 10" Twin Red Oak (1/4S 7/8 NBT), N 78° E, 9.6 Feet



12" Red Oak (1/4S 7/8 NBT), S 32° E, 53.0 Feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner placed 40.00 chains North of Section Corner 7-8-17-18.

Streams North and South check well with calls of Original notes.

Marked 6" Soft Maple 4.00 chains North on Log Road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8/11/1966  
REGISTERED LAND SURVEYOR