

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 34 W


Houghton COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 17-18-19-20

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED ~~8/18~~ 5/25/66

WITNESSES TO CORNER..... 9" Soft Maple (S18 NBT), N 62° W, 13.8 Feet



6" Hard Maple (S17 NBT), N 82° E, 14.0 Feet

9" Soft Maple (S19 NBT), S 74° W, 6.0 Feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner placed on line of old blazes North and South and recorded
distance from Streams to North.

No evidence of Original Corner. The half mile to South is 43.10 chs. Record--
40.00 chains. Half mile to West is 41.33 chs, Record - 40.00chs. Found the Original
1/4 Corner 1/2 mile West.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8/11/1966
REGISTERED LAND SURVEYOR