

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>53N</u> R <u>35W</u>	<u>813</u>
	T <u>53N</u> R <u>35W</u>	<u>C13</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

C13 Jun 12 2007  
 813 Jun 11 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(B13) Standard Quarter corner on the south line of Section 31. 1845 - Established by Wm.A.Burt, Deputy Surveyor, on the Township line between Section corner 40.00' chains east and Township corner 41.49 chains west. Set post. Sugar 12 N61E 12 links, Sugar 12 N60W 31 links.  
 (C13) Standard Section corner between Sections 31 and 32. 1840 - Established by Wm.A.Burt, Deputy Surveyor. Set post corner of Sec. 31 & 32. Birch 20 N54E 25 links, Sugar 16 N10W 16 links. 1940 - W.A.Maara, for Copper Range Company, erroneously notes this corner to be common with the Standard Section corner. He found a 1 1/4" I.P. 1.5' above ground and noted the following: 14" Y.Birch marked by cruisers N1E 19.4', 7" S.Map. marked by cruisers N69E 27', Put Y.tag on 7" R.Map.(crotched) N44W 28.5', Marked 4" S.Map. S28E 16.4'. The original GLO plat for T52N-R35W shows the Closing Section corner 8 links west of the position for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B13) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on the Township line between Township corner 2743.46' west and Standard Section corner 2644.94' east, proportionate to the original record. The corner falls 16' south of the center of an E-W gravel drive.  
 (C13) The original post and accessories were not recovered. Found a 1" I.pipe, origin unknown, projecting 1.7' above ground. This pipe was found 5.17' east of a 1 1/4" ID pipe, origin unknown, which the undersigned has accepted as marking the position of the Closing Corner between Sec. 5-6 T52N-R35W. Accepted the 1" pipe as the best available evidence of the position of the original Standard Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap, set flush with ground. Set measuring nails in:	(C13) Found 1" ID I.pipe. Set measuring nails in:
7" Sugar S88W 29.95' no marks made	14" Sugar S13E 14.85' mrkd "S5 NBT"
6" Poplar N13W 41.9' do	5" Sugar N80W 12.35' "S31 NBT"
6" Poplar N19E 38.95' do	6" Sugar N43W 15.45' "S31 NBT"
The NW cor. of mobile home bears S01W 19.9' MDNR monument at the N1/4 Sec. 6 T52N-R35W is West, 5.25'. Bearings magnetic. Dist. to trees are to nail w/MDNR tag.	7" Sugar N66E 3.0' "S32 NBT"
	Distances are to nail with MDNR tag.
	Fd. 1.25" ID I.P. West 5.17'
	Bearings are magnetic. Set sq'd Sugar post adjacent.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/12/07