

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 53N R 35W	K11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S <u>25</u> T 53N R 35W	L10
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on K11 10/07/2008
L10 10/13/2008 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(K11) Corner common to Sections 25-26-35-36. 1846 - Established by S.W.Higgins Deputy Surveyor. Set
post. Cedar 20" N45E 10 links, Cedar 20" S75W 28 links. 1961 - Remonumented by Billy D. Buckler RLS
from the original BTs. The Cedar NE was found with scribing plain, the Cedar SW no marks. Set
1" I.pipe with 4" brass cap. 12" Cedar N62E 16 links, 12" Elm N59W 32 links.

(L10) Center of Section 25. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K11) Found the 1961 monument in good condition and at record bearing and distance from the 1961
NBTs. The Elm NW is dead and down, a 3 ft. tall stub remains. The Cedar SE is in good condition.
The original BT Cedar N45E was recovered at record bearing and distance, down, badly rotted, with
scribed "3" visible. Accepted the monument as a careful and faithful perpetuation of the position of
the original corner.

(L10) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K11) Fd. 1" ID I.pipe with 4" brass MI Dept. of
Conservation cap. Set measuring nail with
MDNR tag in the side of:
13" Cedar N67E 11.35' old marks 1961 NBT
10" Cedar S54E 2.25' mrkd "S36 NBT" old signatures
5" Cedar S63W 18.25' mrkd "S35 NBT"
16" Y.Birch N06W 21.25' "S26 NBT"
Sq'd cedar post adjacent.
Bearings are magnetic.

(L10) Set 1" IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
22" Hemlock N30E 10.6' mrkd "C1/4 BT"
9" Sugar S13E 28.7' do
6" Sugar S49W 16.1' do
13" Cedar N10W 40.1' do
Sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/01/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

