

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>53N</u> R <u>35W</u>	<u>K10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26	●	25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 10/29/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(K10) Quarter corner common to Sections 25 and 26. 1846 - Established by S.W.Higgins Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Sugar 8" N60E 7 links, Sugar 8" S55W 17 links. 1965 - Billy D. Buckler RLS found a 1" iron pipe "placed by an unknown Surveyor. Found no evidence of original witnesses. Iron pipe appears to have been set midway on the mile and to the east of a straight line". 13" Hard Maple S05W 35 links, 12" Hard Maple N72W 38 links, 8" Soft Maple N71E 65 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K10) Found the Iron pipe of record, at record bearing and distance from the 1965 witnesses. The pipe is located N42E 96.1' from the proportionate position midway and on the Section line between Section corners. Found no acceptable evidence supporting this location as the position of the original corner and I note that Mr. Buckler's statement that the pipe "appears to have been set midway on the mile..." is erroneous. I did not accept the pipe was marking the position of the original corner. Since the original post and accessories were not recovered, I reestablished the corner midway and on the Section line between Section corners 2672.72' north and south. Drove the iron pipe of record flush with ground surface.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K10) Set 1"ID I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 18" Sugar N09E 14.2' mrkd "1/4S NBT"  
 8" Sugar N82E 22.2' do  
 10" Sugar S10E 18.7' do  
 5" Sugar N62W 22.3' do  
 Sq'd Sugar post adjacent.  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 12/01/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971