

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 53N R 35W	L9
	T 53N R 35W	M9
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on L9 10/29/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L9) Quarter corner common to Sections 24 and 25. 1846 - Established by S.W.Higgins Deputy Surveyor. Set post midway and on the Section line between Section corners 39.92 chains east and west. Hemlock 12" N05W 26 links, Sugar 12" S05E 30 links. 1966 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Corner recorded in 1976 by K.L.Sackett RLS. Set 1" pipe with 4" alum. 8" Y.Birch S37W 19.2', 7" Y.Birch N35W 14.0'

(M9) Corner common to Sections 24-25 T53N-R35W and Sections 19-30 T53N-R34W. 1845 - Established by W.A.Burt Deputy Surveyor. Set post. Hemlock 14" S40E 47 links, Fir 8" N30W 26 links. 1846 - Additional B.T. by S.W.Higgins Deputy Surveyor: B.Ash 12" N60E 40 links. 1957 - Remonumented by Billy D. Buckler RLS "from one black ash B.T. bearing N60E 40 links. Found overgrowth and scribe marks very plain. Tree down". Set 1" pipe with 4" brass cap. 10" Y. Birch N35W 26.5 links, 12" Y.Birch S58E 46 links, 10" Y.Birch N57E 53 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L9) Found the monument described in the 1976 record, in good condition, and at record bearing and distance from the 1976 witnesses. Found no record of subsequent work dependent upon the position of the 1976 monument. My measurements show that the 1976 monument was installed S65W 14.5' from the midway position intended and I did not accept the monument of record as marking the position of the corner. Reestablished the position for the corner midway and on the Section line between Section corners 2558.89' east and west. Removed the 1976 monument.

(M9) Found the 1957 monument in good condition and at record bearing and distance from the 1957 witnesses. The Y.Birch NW is in good condition with overgrown blazes, the Y.Birch SE is cut stump with old blaze visible, the Y.Birch NE is dead and down. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Sugar S44E 3.3' mrkd "1/4S NBT"
 8" Y.Birch S33W 16.8' do
 10" Y.Birch N73W 21.5' do (also 1976 NBT)
 6" Y.Birch N18W 9.8' do
 Sq'd cedar post adjacent.
 Bearings are magnetic.

(M9) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 13" Y.Birch N27W 17.8' old blazes 1957 NBT
 4" Sugar N53E 6.0' mrkd "S19 NBT"
 11" Hemlock S45E 23.0' "S30 NBT"
 9" Y.Birch S61W 29.3' "S25 NBT"
 Sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/01/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

