

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 53N R 35W	L11
	T 53N R 35W	M10
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on L11 10/29/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L11) Quarter corner common to Sections 25 and 36. 1846 - Established by S.W.Higgins Deputy Surveyor midway and on the Section line between Section corners 40.09 chains east and west. Set post. Cedar 14" N63E 18 links, Balsam 10" N50W 45 links. 1990 - Reestablished midway and on line between Section corners by K.L.Sackett RLS. Set 1"IDx32" iron pipe with 4" aluminum cap. 5" Sugar S06E 10.7', 4" Sugar N67E 16.6', 4" Sugar N16W 35.8'.

(M10) Quarter corner common to Section 25 T53N-R35W and Section 30 T53N-R34W. 1845 - Established by W.A.Burt Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Fir 6" S78E 31 links, Fir 8" N55W 5 links. 1961 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. No original evidence found. Set 1" pipe with 4" brass cap. 7" Y.Birch N38W 09 links, 14" H.Maple N86E 31 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L11) Found the 1990 monument in good condition and at record bearing and distance from the 1990 NBTs. The Sugars NE and SE are in good condition with scribing visible. The Sugar NW is dead and down. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(M10) The original post and accessories were not recovered. Found the 1961 monument in good condition and at record bearing and distance from the Y.Birch NBT NW marked in 1961. I found no record of subsequent work dependent upon the position of the 1961 monument. My measurements show that the 1961 monument was installed in an erroneous position 25.1' south of the position intended in 1961 and I did not accept it as marking the position of the corner. Reestablished the corner midway and on the Section line between Section corners 2638.70' north and south. Removed the 1961 monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Sugar N69E 16.8' old marks 1990 NBT
 7" Sugar S04E 10.9' do do
 9" Sugar S37E 17.1' mrkd "1/4S NBT"
 6" Sugar N66W 18.0' do
 Sq'd Cedar post adjacent.
 Bearings are magnetic.

(M10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Y.Birch S44E 6.4' mrkd "1/4S NBT"
 10" Y.Birch S14W 20.8' do (also 1961 NBT)
 7" Y.Birch S75W 12.1' do
 8" Sugar N14W 11.2' do
 Sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/01/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities