

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|                                       |                           |               |  |
|---------------------------------------|---------------------------|---------------|--|
| <u>Houghton</u><br>(County)           | Located In:               | Corner Code # |  |
| 1. Public Land Survey                 | T <u>53N</u> R <u>35W</u> | <u>L7</u>     |  |
|                                       | T _____ R _____           | _____         |  |
|                                       | T _____ R _____           | _____         |  |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____         |  |
|                                       | S _____ T _____ R _____   | _____         |  |
|                                       | S _____ T _____ R _____   | _____         |  |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____         |  |
|                                       | S _____ T _____ R _____   | _____         |  |
| 4. Lot No. _____, Recorded Plat _____ |                           |               |  |
| 5. Private Claims _____               |                           |               |  |

Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Stephan J. Szyszkoski, in a field survey on 01/14/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(L7) Quarter corner common to Sections 13 and 24. 1976 - Recorded by K.L.Sackett RLS with the explanation that this corner was reestablished June 16, 1966 by Regional Land Surveyor Billy D. Buckler RLS but not recorded. Found wood post set by unknown persons midway between two section corners. Set 1"ID pipe with 4" aluminum cap. 13" Red Oak S57E 23.5', 8" Sugar N61W 19.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L7) Recovered the 1966 monument in good condition and at record bearing and distance from the 1966 witnesses. The Red Oak SE is in good condition with overgrown blazes. The Sugar NW is dead and down. Left the monument in place. This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L7) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 22" Oak S52E 22.7' old blazes 1966 NBT  
 11" Maple South 25.4' mrkd "1/4S NBT"  
 7" Sugar S88W 25.1' do  
 5" Sugar N13E 27.3' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/09/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995